

June 7, 2017

PROJECT: New Two Family/Office Building

S/B/L: 106.10/2/16

Marble Ave and St. George Street

Ref. No.: 1613

PROJECT DESCRIPTION - PROPOSED REVISION TO APPROVED SITE PLAN

At this time, we respectfully request the Board to consider minor changes to the approved Site Plan for the project mentioned above. The changes are as follows and are shown on the attached SP-1 drawing:

- Rotate parking to enter the site straight in from St. George Place.
- Reduce overall parking area; approved was 2.0' from the west property line and the proposed is 20.8'.
- Reduce overall impervious parking surface area by approximately 27%, from 1,857 SF to 1,316 SF.
- Provide same approved fence at this location to provide screening to neighboring property.
- Reduce the approved curb cut from 20' to 12'.
- Provide one 12' curb cut to house/garage and one 12' curb cut to parking area.
- Four parking spots are required and four parking spots are provided.
- Locate trash bins as shown and provide both plantings and fence screening.

If you have any questions, please call me at 914-747-3500 (o) or 914-714-5607 (c). Thank You.

Very truly yours, DIMOVSKI ARCHITECTURE PLLC

Steve Dimovski

Steve Dimovski Associate

NEW SINGLE FAMILY RESIDENCE REALTY RESIDENCE

LIST OF DRAWINGS

NOTES & LEGEND, ZONING ANALYSIS, SITE PLAN, DETAILS

NOTES & LEGEND, LIST OF DRAWINGS, BASEMENT PLAN/ FOOTING/FOUNDATION PLAN, TYP. WALL SECTION, DETAILS, AVERAGE GRADE DIAGRAM

-NEW POURED CONCRETE WALL

-NEW 2"x6" STUD WALL WITH 1/2" TYPE "X" FIRECODE GYPSUM WALL BOARD

- -NEW SMOKE ALARM/DETECTOR
- -NEW CARBON MONOXIDE DETECTOR

General Notes

I. CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH ALL SEDIMENT AND EROSION CONTROL PRACTICES. THE SEDIMENT AND EROSION CONTROL PRACTICES ARE TO BE INSTALLED PRIOR TO ANY MAJOR SOIL DISTURBANCES, AND MAINTAINED UNTIL PERMANENT PROTECTION IS ESTABLISHED.

2. TIMELY MAINTENANCE OF SEDIMENT CONTROL STRUCTURES IS THE RESPONSIBILITY OF THE CONTRACTOR. ALL STRUCTURES SHALL BE MAINTAINED IN GOOD WORKING ORDER AT ALL TIMES. THE SEDIMENT LEVEL IN ALL SEDIMENT TRAPS SHALL BE CLOSELY MONITORED AND SEDIMENT REMOVED PROMPTLY WHEN MAXIMUM LEVELS ARE REACHED OR AS ORDERED BY THE ENGINEER. ALL SEDIMENT CONTROL STRUCTURES SHALL BE INSPECTED ON A REGULAR BASIS, AND AFTER EACH HEAVY RAIN TO INSURE PROPER OPERATION AS DESIGNED. AN INSPECTION SCHEDULE SHALL BE SET FORTH PRIOR TO THE START OF CONSTRUCTION.

3. THE LOCATIONS AND THE INSTALLATION TIMES OF THE SEDIMENT CAPTURING STANDARDS SHALL BE AS ORDERED BY THE ENGINEER, AND IN ACCORDANCE WITH THE STANDARDS SET FORTH IN THIS MANUAL.

PLACED IN A STABILIZED STOCKPILE OR FILL AREA. ALL TOPSOIL REQUIRED FOR FINAL GRADING AND STORED ON SITE SHALL BE LIMED, FERTILIZED, TEMPORARILY SEEDED AND MULCHED WITHIN 14 DAYS.

5. ANY DISTURBED AREAS THAT WILL BE LEFT EXPOSED MORE THAN 21 DAYS AND NOT SUBJECT TO CONSTRUCTION TRAFFIC, SHALL IMMEDIATELY RECEIVE TEMPORARY SEEDING. MULCH SHALL BE USED IF THE SEASON PREVENTS THE ESTABLISHMENT OF A TEMPORARY COVER. DISTURBED AREAS SHALL BE LIMED AND FERTILIZED PRIOR TO TEMPORARY SEEDING.

6. ALL DISTURBED AREAS WITHIN 500 FEET OF AN INHABITED DWELLING SHALL BE WETTED AS NECESSARY TO PROVIDE DUST CONTROL.

7. THE CONTRACTOR SHALL KEEP THE ROADWAYS WITHIN THE PROJECT CLEAR OF SOIL AND DEBRIS AND IS RESPONSIBLE FOR ANY STREET CLEANING NECESSARY DURING THE COURSE OF THE PROJECT.

8. SEDIMENT AND EROSION CONTROL STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE DRAINAGE AREA HAS BEEN PROPERLY STABILIZED BY PERMANENT MEASURES

9. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH CURRENT EDITION OF "WESTCHESTER COUNTY BEST MANAGEMENT PRACTICES MANUAL FOR EROSION AND SEDIMENT CONTROL".

10. ALL SITE DISTURBED AREAS SHALL BE CONTAINED ON THE PROPERTY WITH NO RUNOFF ON TO ADJACENT PARCELS AND VILLAGE ROADS.

ZONING DATA TABLE

DESCRIPTION OF WORK:TWO FAMILY RESIDENCE \$ 2 CAR GARAGE

| ZOI | NE: RO-3 | | |
|---|--------------|----------|--|
| USE | REQUIRED | EXISTING | PROPOSED |
| MAIN BUILDING | | | |
| LOT AREA (SQUARE FEET) | 7,500 | N/A | (1) 5,000 |
| LOT FRONTAGE (FEET) | 75' | N/A | 100' |
| LOT WIDTH (FEET) | 75' | N/A | 100' |
| LOT DEPTH (FEET) | 90' | N/A | (2) 50' |
| FRONT YARD SETBACK (FEET) | 30' | N/A | (3) 10.5' |
| FRONT YARD SETBACK (FEET) | 30' | N/A | (4) 13' |
| SIDE (FEET) | 8' | N/A | 41' |
| REAR (FEET) | 25' | N/A | (5) 8' |
| MIN GROSS AGGREGATE FLOOR AREA PER DWELLING UNIT (SQUARE FEET) | 800 SF | N/A | 880 SF (DWELLING 1) 1,370 SF (DWELLING 2) |
| MAX HEIGHT (STORIES/FEET) | 2 1/2 OR 30' | N/A | 2 1/2/ LESS THAN 30' |
| MAXIMUM BUILDING COVERAGE (%) | 30 % | N/A | 27.8 % |
| 10' SETBACK FOR PARKING FROM PROPERTY LINE | 10' | N/A | (6) 2' / 10' (9) |
| 12' CURB-CUT REQUIRED | 12' | N/A | (7) 20' / 12' (10) |
| 30' FRONT YARD SETBACK FOR PARKING | 30' | N/A | (8) 15'/ 18.8' (II) |

VARIANCE(S) REQUIRED

ALL VARIANCES WERE GRANTED PER SEPTEMBER 29, 2016 ZONING BOARD MEETING

(I) - LOT AREA 7,500 SF IS REQUIRD, HAS 5,000 SF, THEREFORE A 2,500 SF VARIANCE IS NEEDED.

(2) - LOT DEPTH - 90' IS REQ'D, HAS 50', THEREFORE A 40' VARIANCE IS NEEDED.

(3) - FRONT YARD SETBACK - 30' IS REQ'D, HAS 10.5', THEREFORE A 19.5' VARIANCE IS NEEDED

(4) - FRONT YARD SETBACK - 30' IS REQ'D, HAS 13', THEREFORE A 17' VARIANCE IS NEEDED

(5) - REAR YARD SETBACK - 25' IS REQ'D, HAS 8', THEREFORE A IT' VARIANCE IS NEEDED (6) - PROPERTY LINE SETBACK FOR PARKING - 10' IS REQ'D, HAS 2', THEREFORE AN 8' VARIANCE IS NEEDED.

(7) - MAX. CURB-CUT REQUIRED - 12' IS REQ'D, HAS 20', THEREFORE AN 8' VARIANCE IS NEEDED

(8) - FRONT YARD SETBACK FOR PARKING - 30' IS REQ'D, HAS 15', THEREFORE AN 15' VARIANCE IS NEEDED.

YARIANCES REQUIRED BASED ON REVISED DRAWINGS DATED 6/1/2017.

(9) - PROPERTY LINE SETBACK FOR PARKING - 10' IS REQ'D, HAS 10', THEREFORE VARIANCE IS ELIMINATED.


(10) - MAX. CURB-CUT REQUIRED - 12' IS REQ'D, HAS 12', THEREFORE VARIANCE IS ELIMINATED

(II) - FRONT YARD SETBACK FOR PARKING - 30' IS REQ'D, HAS II.2', THEREFORE AN 18.8' VARIANCE IS NEEDED.


THE ANTI- TRACKING PAD SHALL UNIFORMLY GRADED TO PRODUCE THE ENTRY AND EXIT PATH TO THE SITE FOR ALL ONSTRUCTION EQUIPMENT.

THE PAD SHALL BE MAINTAINED OF SUFFICIENT GRADING AND STONE SURFACE TO CAPTURE ALL SOILS AND SEDIMENT FROM EQUIPMENT TIRES PRIOR TO SUCH EXITING FROM THE SITE.

STONE SHALL BE REPLENISHED OR REPLACED AS NECESSARY TO ASSURE SUFFICENT CAPTURE OF SEDIMENT AT THE CONSTRUCTION SITE. ANY SEDIMENT TRACKED OFF THE SITE SHALL BE IMMEDIATELY CLEANED, SWEPT AND REMOVED BY THE CONTRACTOR.




ANTI-TRACKING PAD DETAIL SCALE: 3/4"=1'-0"



STONE/ CONCRETE CURB DETAIL SCALE: 3/4"=1'-0"

ALL JOINTS TO BE CEMENTED.



INSTALLATION NOTES

TOE-IN METHOD

I. EXCAVATE A 4 INCH * 4 INCH TRENCH ALONG THE LOWER PERIMETER OF THE SITE.

SECTION A

JOINING SECTIONS OF FENCING

2. UNROLL A SECTION AT A TIME AND POSITION THE POSTS AGAINST THE BACK (DOWNSTREAM) WALL OF THE TRENCH (NET SIDE AWAY FROM DIRECTION OF FLOW).

3. DRIVE THE POST INTO THE GROUND UNTIL THE NETTING IS APPROXIMATELY 2 INCHES FROM THE TRENCH BOTTOM.

4. LAY THE TOE-IN FLAP OF FABRIC ONTO THE UNDISTURBED BOTTOM OF THE TRENCH, BACKFILL THE TRENCH AND TAMP THE SOIL. STEEPER SLOPES REQUIRE AN INTERCEPT TRENCH.


5. JOIN SECTIONS AS SHOWN ABOVE.


Silt Fence

OFF-STREET PARKING REFERENCE SECTION (185 ATTACHMENT 7 SCHEDULE VII) TWO FAMILY DWELLING

2 PER DWELLING = 4 PARKING SPOTS

2 FAMILY DWELLINGS = 4 PARKING SPOTS






I. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE.

2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 12.

3. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED WITH EITHER SILT FENCING OR STRAWBALES, THEN STABALIZED WITH VEGETATION OR COVERED. 4. SEE SPECIFICATIONS(THIS MANUAL) FOR INSTALLATION OF SILT FENCE.



INSTALLATION NOTES

I. BALES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES.

2. EACH BALE SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF 4" 3. BALES SHALL BE SECURELY ANCHORED IN PLACE BY STAKES OR RE-BAR DRIVEN THROUGH THE BALES. THE FIRST STAKE IN EACH BALE SHALL BE ANGLED TOWARD PREVIOUSLY LAID BALE TO FORCE BALES

4. BALES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFULLNESS SO AS NOT TO BLOCK OR IMPEDE STORM FLOW OR

Strawbale Sediment Barriers

REVISION #1 REVISION #2 PLANNING BOARD REVISION #3 ZONING BOARD SUBMISSION 2 **REVISION #4** PLANNING BOARD 10-13-2016 PLANNING BOARD REVISION #6 LANNING BOARD REVISION #7 PLANNING BOARD REVISION #8 LANNING BOARD REVISION #9 6//7/2017 DRAWING TITLE:

REV. & ISSUE

LANNING BOARD

PLANNING BOARD 3-17-2016

4-20-2016

DATE: FEBRUARY 24, 2017 PROJECT NO.: 1613 DRAWN BY: WMP CHECKED BY: SGD/PD